


Caius Colfer

DESIGN PORTFOLIO & CV

VERSION 1.0 - 2020

A conscientious, professional individual, highly organised and efficient, with a thorough and precise approach to all tasks undertaken. Punctual throughout working life, whilst able to manage time effectively and prioritise workload. Experienced at working to tight deadlines and under considerable pressure. Friendly and approachable, with good interpersonal and customer relations skills.

01

Sixth Form

A Levels – Fine Art, Geography
and Business Studies

02

Higher Education

Architecture BSC (HONS) 2:1
Anglia Ruskin University

03

Further Qualifications

AutoCAD – Management Revit
Course & Introductory Revit
Draughts Person Crash Course

WORK EXPERIENCE

01

OFFICE MANAGER/ SENIOR ARCHITECTURAL TECHNICIAN

July 2016 – Present

Grafik Architecture

Management of staff across the North and Midlands offices overseeing up to 10 live projects at any one time. Day to day dealings with our UK National house builder client base, local authorities, consultants, contractors and suppliers, both over the phone and face to face within full design team meetings or on site. Conducting appraisals, performance reviews and overseeing the recruitment process across the two offices. Drafting feasibility schemes and site layout sketch proposals, full planning application drawing packs up to and above 1000 units and full technical drawing packages across multiple disciplines. Continual review and management of NHBC conditions across all sites to efficiently clear any conditions, working closely with the client and consultants alike, within the role of lead consultant. Attendance on site and day to day liaison with site managers and contractors. Regular attendance at networking events and conferences, across the Midlands and North West to further develop our client and consultant relationships, whilst also bringing in new work and opportunities.

WORK EXPERIENCE

02

ARCHITECTURAL TECHNICIAN

March 2008 – July 2016

DJW Architectural Designs

Completion of multi-disciplinary projects from inception to completion across all stages, including an award-winning school refurbishment and sports complex. Liaising with local authorities, consultants and contractors, whilst working closely with the client throughout the duration to ensure satisfaction and efficiency. Design and project management of large bespoke dwellings ranging from 4 to 7 bedrooms with one-off private clients and developers/contractors. Dealing with day to day site queries and attendance at design team meetings.



Examples

EARLIEST TO CURRENT YEAR




01

**Trumpington Meadows,
Cambridge, Cambridgeshire**

Barratt Homes

2016

Sainsbury's store and further retail outlets. Two apartment blocks comprising of 42 units and central 'feature'access corridor/ amenity square.




N
Existing Sub Station
2 No. bollards @ 1.5m centres
3 No. bollards @ 1.5m centres
Cyclists dismount
Cyclists dismount at end of footpath in local centre
Demountable bollard at end of footpath in local centre
Cyclists dismount
Cyclists dismount at end of footpath in local centre
Cyclists dismount
Cyclists dismount at end of footpath in local centre
Cyclists dismount
Cyclists dismount

02


LIDL Store & 'Aspect' Apartments, Hersham, Surrey


Crest Nicholson

2016


Ground floor shell & core Lidl store and 38 No. apartments with external podium deck terrace.









THIRD FLOOR - 1:25 @ A1



SECOND FLOOR - 1:25 @ A1



FIRST FLOOR - 1:25 @ A1



GROUND FLOOR - 1:25 @ A1

NOTE:
THIS WORKING DRAWING IS TO BE READ IN CONJUNCTION WITH THE CREST STANDARD CONSTRUCTION NOTES AND THE STANDARD WORKMANSHIP AND MATERIALS SPECIFICATION

BLOCK SPECIFICATION:


Ground floor:
Inner leaf 140mm Aggregate blockwork, 600-800 Kgm3. 7.3n compressive strength
Outer leaf 100mm Aggregate blockwork, 600-800 Kgm3. 7.3n compressive strength

First floor:
Inner leaf 100mm aircrete blockwork 600-800kgm3. 7.3n compressive strength
Outer leaf 100mm aggregate blockwork medium density. 7.3n compressive strength


Second and 3rd floor
Inner leaf 100mm aircrete blockwork 600-800kgm3. 3.6n compressive strength
Outer leaf 100mm aggregate blockwork medium density. 3.6n compressive strength

Party wall first floor:
2 leaves 100mm, 600-800kgm3 aircrete, 7.3n compressive strength

Party wall second and 3rd floor:
2 leaves 100mm, 600-800kgm3 aircrete, 3.6n compressive strength



Roof section - 1:25 @ A1



Half landing joist section - 1:25 @ A1

RECORD DRAWING

Rev.	Description.	Date.	Initial.
C11	Timber stud introduced to 3rd floor	10.07.19	CC
C10	Armstrong suspended ceiling added as requested	26.06.19	CC
C9	Half landing support revisions	23.05.19	CC
C8	Gutter area revised to show tapered gutter.	13.05.19	CC
C7	Section through glazing shown.	21.08.18	CC
C6	DPM added to columns as requested by NHBC	15.03.18	CC
C5	Ceiling reverberation treatment added, & unheated space note, roof detail added	23.02.18	DS
C4	Finishes revised	07.02.18	CC
C3	G.FLOOR STAIR REVISIONS	06.02.18	CC
C2	JOIST FINISH REVISIONS	26.01.17	CC
C1	CONSTRUCTION ISSUE	12.01.18	CC
T1	ISSUED FOR TENDER.	22.12.2017	MH/DS

Crest Nicholson Ltd.
Crest House
Pyrcroft Road
Chertsey
Surrey
KT16 9GN
Tel: 01932 580555
Fax: 08703 363990
Internet: www.crestnicholson.com

Site: LIDL - Molesey Rd, Hersham


Drg Title: REDIDENTIAL STAIR CORE 01
PLANS & SECTION


RECORD DRAWING

Scale: 1:25@A1 | Date: Dec 2017 | Drawn: MH | Checked: DS

CAD Ref: 17-2663_05_stair sections.dwg | NHBC Approval Ref:


Drawing No: 14794-1601 | Revision: C11



NOTE:
THIS WORKING DRAWING IS TO BE READ IN CONJUNCTION WITH THE CREST STANDARD CONSTRUCTION NOTES AND THE STANDARD ASSEMBLIES OF WORKMANSHIP AND SPECIFICATION
DRAWING DETAIL REFERENCES -
GROUND WORK DETAIL DRAWINGS 14794-990 TO 992
NOTE FOR ALL STEPS, STRADDLES AND EXTERNAL LEVELS, REFER TO CIVIL ENGINEERS / INTERNAL WORKS / LANDSCAPE ARCHITECTS DRAWINGS.
INCOMING SERVICES (GAS / WATER / ELECTRIC / FIBRE OPTICS) AND METER POSITIONS / LOCATIONS TO BE CONFIRMED. REFER TO CIVIL ENGINEERS DRAWINGS FOR EXIT LANDS KERBS.
BLOCK SPECIFICATION:
Ground floor:
Inner leaf 140mm aggregate blockwork, 400-800 kgm3. 7.3n compressive strength
Outer leaf 100mm Aggregate blockwork, 600-800 kgm3. 7.3n compressive strength
First floor:
Inner leaf 140mm aircrete blockwork 600-800kgm3. 7.3n compressive strength
Outer leaf 100mm aggregate blockwork medium density. 7.3n compressive strength
Second and 3rd floor:
Inner leaf 140mm aircrete blockwork 600-800kgm3. 3.6n compressive strength
Outer leaf 100mm aggregate blockwork medium density. 3.6n compressive strength
Party wall first floor:
2 leaves 100mm, 600-800kgm3 aircrete, 7.3n compressive strength
Party wall second and 3rd floor:
2 leaves 100mm, 600-800kgm3 aircrete, 3.6n compressive strength
NOTE. Incoming Services to be read in conjunction with 14794-4000.
Note** Dashed lines indicate block walls to be constructed by Lidl.
Recess to structural slab to accommodate Freezer/Chiller
Note** Dashed lines indicate block walls to be constructed by Lidl.
75mm recess to structural slab to accommodate Sluice
Note** Dashed lines indicate block walls to be constructed by Lidl.
NOTE. Incoming Services to be read in conjunction with 14794-4000.
NOTE. Incoming Services to be read in conjunction with 14794-4000.
HIGH LEVEL RUN THROUGH STAIR CORE WINDOW
Ref. door to under hall landing
WALL CONSTRUCTION LEGEND
GROUND FLOOR GENERAL ARRANGEMENT
1:100 @ A0
RISK SCHEDULE
DESCRIPTION OF RISK & ACTION
Risk - Handling of large / heavy tar gauge lintel
Action - A method statement to be provided by supplier and approved prior to commencement on site
FOUNDATION NOTES
Refer to structural engineers site specific foundation plans.
Foundation depths to be agreed on site with the local building inspector and to conform to NHBC requirements.
Drawing to be read in conjunction with coordinated site setting out plan by civil engineer.
Provide concrete lintels over doors where passing through walls.
Refer to co-ordinated Civil Engineers drawings for RWP & SVP locations
NOTE ** ANY BEAMS, BEAM UNITS, STRUCTURAL PIERS, EDGE BEAMS, WINDPOSTS, NON-BEARING SUPPORTS OR PADSTONES INDICATED ON THIS DRAWING ARE SUBJECT TO FULL CIVIL ENGINEERS DESIGN. CREST CANNOT BE HELD RESPONSIBLE FOR INFORMATION PROVIDED BY OTHER CONSULTANTS
RECORD DRAWING
C9 Bike racks added to 2 no. cycle stores 07.09.19 CC
C8 General Coordination revisions 26.09.18 CC
C7 Ramp added to Sales 10.08.18 CC
C6 Concrete slab dimensions added. 07.06.18 GAT
C5 Wall legend added 05.04.18 GAT
C4 Movement Joints added 13.11.18 CC
C3 Note outlining block work to be built by UDL added 07.01.18 CC
C2 LEVELS BLOCK SPECIFICATION ADDED 29.01.18 MH/DS
C1 CCTV DUCT ADDED TO F/F ROOM. ISSUED FOR CONSTRUCTION 22.01.2018 MH/DS
T5 FURTHER DRAWINGS ADDED TO EXTERNAL & INTERNAL DRAWINGS 04.01.2018 MH/DS
T4 STAIR CORE LAYOUTS REVISED. TEMPORARY DOORS FOR SALES OFFICE SHOWN. DRAWING ADDED TO SUIT NEW STAIR CORE LAYOUTS. DIMENSIONS ADDED TO EXTL DRAWINGS. 22.11.2017 MH/DS
T3 EXTERNAL WALL ON CORE LINE IS BLOCK 215mm 07.11.17 CC
T2 ISSUED FOR TENDER 01.11.2017 MH/DS
P9 RE-ISSUED AS DELIVERED & NOTED 31.10.2017 MH/DS
P8 NOT USED
P7 RE-ISSUING AS DELIVERED & NOTED 19.10.2017 MH/DS
P6 RE-ISSUING AS DELIVERED & NOTED 18.10.2017 MH/DS
P5 HORIZONTAL GRIDS REVISED & RENUMBERED. FACADE GLAZING SET OUT TO SEE STANDING & INTERNAL COLUMNS ADJUSTED. INTERNAL DRAINAGE ADJUSTED TO ACCOMMODATE BEVELLED MENTS EXTERNAL DRAINAGE CHANGES. REVISED AREA SCHEDULE ADDED. CELL & AISLE LABELS ADDED. WEIGHT PROJECTION BUFFALO FREEZER/CHILLER & WAREHOUSE. RIBE EQUAL DOORS ADDED TO 1226 O/O. HANDING DIMENSIONS SHOWN BETWEEN CONSUMER DOOR EL. 03.10.17 MH/MG
P4 ISSUED FOR COMMENT. STRUCTURAL ENGINEER COMMENTS INCORPORATED. CLOUDED IN RED. COMMENTS/UPDATES REQUESTED FROM LIDL MARKED IN BLUE. 21.09.17 MH/MG
P3 ISSUED FOR COMMENT. INTERNAL COLUMNS THICKENED TO 254mm. GRID LINES ADJUSTED TO SUIT. INTERNAL CAVITY WALLS INTRODUCED TO ACCOMMODATE TRUSSED COLUMNS. 14.09.17 MH/MG
P2 ISSUED FOR COMMENT. ACTION NOTES ADDED FOR STRUCTURAL ENGINEER (NOS & MB). (BLUE). CHANGES TO GRID LINES & COLUMNS ADDED. GRID REVISED TO SUIT LATEST STRUCTURAL COMMENTS. 13.09.17 MH/MG
P1 ISSUED FOR COMMENT. 05.09.17 MH/MG
Rev. Description. Date. Initial.
Crest Nicholson Ltd.
Crest House
Pyrcroft Road
Chertsey
Surrey
KT16 0QN
Tel: 01932 580555
Fax: 01932 803890
www.crestnicholson.com
Site: LIDL - Maisey Rd - Horsham
Dwg Title: Ground Floor Level General Arrangement
RECORD DRAWING
Scale: 1:100 @A0
Date: Jul 2017
Drawn: MH
Checked: MG
CAD Ref: 17-2603_02_ga plans.dwg
WMC Approval Ref:
Drawing No: 14794-1001
Revision: C9
1:100
0
5m
10m




SECTION A-A
1:20 @ a1

SECTION E-E - cut through step.
1:10







SECTION D-D
1:20 @ a1
(Skeleton elevation of parapet interface with terrace/ balustrade)



SECTION B-B
1:20 @ a1



SECTION C-C
1:20 @ a1



Pipe Penetration Plan
1:5 @ a1

NOTE:
THIS WORKING DRAWING IS TO BE READ IN CONJUNCTION WITH THE CREST STANDARD CONSTRUCTION NOTES AND THE STANDARD WORKMANSHIP AND MATERIALS SPECIFICATION


RISK SCHEDULE

ITEM	DESCRIPTION OF RISK & ACTION
⚠	Specific health & safety risks associated with this house type are highlighted with the caution symbo adjacent to the item of risk. Please refer to risk schedule contained on individual drawing.
	Risk - Handling of large / heavy flat gauge lintel Action: - A method statement to be provided by supplier and approved prior to commencement on site
	Risk - Handling of large / heavy framed & unframed glass sheets. Action - A method statement to be provided by supplier and approved prior to commencement on site
	Unless highlighted there are no specific health & safety risks associated with this house type, as a direct result of our design, apart from the common issues associated with construction that will need to be assessed by a competent contractor prior to the undertaking of any works.

GENERAL NOTES

1. ALL VERTICAL SIZES ARE BASED ON BRICK/BLOCK COURSING. SUB-CONTRACTOR IS TO VERIFY ALL SIZES ON SITE PRIOR TO MANUFACTURE.
2. TO BE READ IN CONJUNCTION WITH:
   14794-10## SERIES GENERAL ARRANGEMENT PLANS
   14794-130## SERIES ELEVATIONS
   14794-135## SERIES SECTIONS
   14794-931 TO 940 CLADDING DETAILS
   14794-941 TO 950 SUPERSTRUCTURE GENERAL DETAILS
   14794-951 TO 960 BALCONY DETAILS
   14794-1750 to 1751 WINDOW & DOOR SCHEDULES
3. ALL GLAZING DIVIDING TERRACES & BALCONIES SHALL BE CARRIED OUT USING SAFETY GLASS AS DEFINED IN BS6262 PART 4 1994 AND BS6206 1981.
4. FINISHES GENERALLY:
   REFER TO SITE SPECIFIC ELEVATIONS AND MATERIALS SCHEDULE FOR FINISHES.
5. REFER TO ARCHITECT'S BLOCK PLANS FOR FINAL LOCATIONS.
6. WORK TO FIGURED DIMENSIONS ONLY. DO NOT SCALE.





LOCATION PLAN
NTS @ a1

Note* Structural supports to balconies to be painted with intumenscent to fabricators recommendation to achive min. 30 minute F/R.

RESIDENTIAL DETAIL

CONSTRUCTION ISSUE

Rev.	Description	Date	Initial
C11	Pipe plans added	25.09.19	CC
C10	Section F-F added	23.07.19	CC
C9	Finishes revised in line with Sub contractors 'recommendations',	16.07.19	CC
C8	Section A-A revised, Section E-E added.	10.07.19	CC
C7	Screed depths indicated	03.06.19	CC
C6	Re-uploaded to 4projects	10.05.19	DS
C5	Steel tray omitted to section B-B & C-C as requested by client	23.04.19	CC
C4	Amendments to steel screed tray as requested by client	12.04.19	CC
C3	Interface detail D-D added	10.04.19	CC
C2	3rd floor external walkway details added	08.02.19	CC
C1	Construction Issue	04.02.19	CC

Crest Nicholson Ltd.
Crest House
Pyrcroft Road
Chertsey
Surrey
KT16 9GN
Tel: 01932 580555
Fax: 08703 363890
Internet: www.crestnicholson.com

Site: LIDL Molesey Road, Hersham

Drg Title: Superstructure Details
Balcony Details Sheet 09


CONSTRUCTION

Scale: 1:20 @ A1 | Date: Jan 2019 | Drawn: CC | Checked: DS


CAD Ref.: 17-2661_12_superstructure_balcony details 951 to 960.dwg | NHBC Approval Ref.:

Drawing No: 14794-955A | Revision: C11


NOTE:
THIS WORKING DRAWING IS TO BE READ IN CONJUNCTION WITH THE CREST STANDARD CONSTRUCTION NOTES AND THE STANDARD WORKMANSHIP AND MATERIALS SPECIFICATION




A - Walkway Soffit Detail
1:5




B - Walkway Soffit Detail
1:5




E - Post Section
1:5



C - Walkway Soffit Detail
1:5



D - Walkway Soffit Detail
1:5



F - Post Plan
1:5


CONSTRUCTION ISSUE

Rev.	Description.	Date.	Initial.
C3	Details added in line with client request	23.08.19	CC
C2	Detail B added	29.01.19	CC
C1	CONSTRUCTION ISSUE	21.12.18	CC

Crest Nicholson Ltd.
Crest House
Pyrcroft Road
Chertsey
Surrey
KT16 9GN
Tel: 01932 580555
Fax: 08703 363960
Internet: www.crestnicholson.com

Site:	LIDL - Molesey Rd, Hersham
Drg Title:	Superstructure Details Soffit Details
	CONSTRUCTION
Scale:	1:5 @ A2
Date:	Apr 2018
Drawn:	CC
Checked:	--
CAD Ref:	
NHBC Approval Ref.:	
Drawing No:	14794-945
Revision:	C3





No.	Date	Amendment	Initials
P3	13.11.19	Ventilation and rainter drainage updated as client comments.	MRG
P2	09.09.19	Drawings prepared for B. Control	CC
P1	25.07.19	Preliminary Issue	CC

No.	Date	Amendment	Initials

Client : James Barnes

Project : Land Adjacent 85 Colchester Road, Maldon

Drawing : Elevations (sheet 1 of 2)

Scale : 1:100 @ A3 | Status : Preliminary | Rev: P3

Date : June 2019 | Dwg No : 19-2943-10

GRAFIK

Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0DZ
T +44 (0)1277 658 233
F +44 (0)1277 658 234
www.grafikuk.com

© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.


03

Private Development
Maldon, Essex

2019

9 No. split level terraced town houses, with RC and king pin retaining wall structure.





No.	Date	Amendment	Initials
P3	13.11.19	Ventilation and rainter drainage updated as client comments.	MRG
P2	09.09.19	Drawings prepared for B. Control	CC
P1	25.07.19	Preliminary Issue	CC

Client : **James Barnes**

Project : **Land Adjacent 85 Colchester Road, Maldon**

Drawing : **Elevations (sheet 2 of 2)**

Scale : **1:100 @ A3**

Status : **Preliminary**

Rev : **P3**


Date : **June 2019**

Dwg No : **19-2943-12**

GRAFIK

Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0DZ
T +44 (0)1277 658 233
F +44 (0)1277 658 234
www.grafikuk.com

© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.



Ground Floor Plan

Scale 1:50

Internal Door Schedule - ALL Plots

Int. Door Reference	Location	Structural Opening W (mm)	Structural Opening H (mm)	Leaf Size W (mm)	Leaf Size H (mm)	Lining or Frame?	Lintel Requirement	Lining Size W (mm)	Lining Size D (mm)	Notes
D01	WC	998	2035	838	1981	Lining	No	93	28	FD30
D02	Utility	998	2035	838	1981	Lining	No	93	28	FD30
D03	Living	998	2035	838	1981	Lining	No	93	28	FD30
D04	Kitchen/Dining	776	2035	826	2040	-	No	-	-	Cottage pushed door, FD30
D05	Bedroom 3	832	2035	762	1981	Lining	No	93	28	FD30
D06	Bedroom 2	998	2035	838	1981	Lining	No	93	28	FD30
D07	Bathroom	998	2035	838	1981	Lining	No	93	28	FD30
D08	Bedroom 1	998	2035	838	1981	Lining	No	93	28	FD30
D09	A/C	756	-	686	-	Lining	No	93	28	Door cut to suit.
D10	Ensuite	832	2035	762	1981	Lining	No	93	28	-

Note: Please refer to internal door details for confirmation of how structural openings are to be measured.

Note: Please refer to elevations for plot handing's and window openings.

Note: CLIENT TO CONFIRM SETTING OUT OF WINDOW WITHIN TIMBER FRAME AND DEPTH OF CILL.

Ground Floor External Window & Door Schedule

Window/ Door Reference	Plots	Location	External Wall S. Opening W (mm)	External Wall S. Opening H (mm)	Head Treatment	Sill Treatment	Approved Document Part Q Compliant	Notes
WGF01	All	Hall	460	1050	Soldier c. (215)	-	Yes - Ref to construction notes	-
DGF01	All	Hall (entrance)	1010	2110	-	-	Yes - Ref to construction notes	ST
DGF02	All	Garage	908	2110	-	-	Yes - Ref to construction notes	ST

Legend: (EW - Egress Window - See Note.) (OG - Obscure Glazing.) (SG - Safety Glass.) (PD - 1225mm wide double patio door with 2no. 750mm wide sidelights.)

First Floor External Window & Door Schedule

Window/ Door Reference	Plots	Location	External Wall S. Opening W (mm)	External Wall S. Opening H (mm)	Head Treatment	Sill Treatment	Approved Document Part Q Compliant	Notes
WFF01	All	Kitchen	750	1050	-	Lead Flashing	Yes - Ref to construction notes	-
WFF02	All	Kitchen	1248	1050	-	Lead Flashing	Yes - Ref to construction notes	E/W
WFF03	6 & 9	Lounge	750	1050	-	Lead Flashing	Yes - Ref to construction notes	-
DFF01	All	Lounge	3310	2110	-	-	Yes - Ref to construction notes	PD, SG, ST

Legend: (EW - Egress Window) (OG - Obscure Glazing.) (SG - Safety Glass.) (PD - 1810mm wide double patio door with 2no. 750mm wide sidelights.)

Second Floor External Window & Door Schedule

Window/ Door Reference	Plots	Location	External Wall S. Opening W (mm)	External Wall S. Opening H (mm)	Head Treatment	Sill Treatment	Approved Document Part Q Compliant	Notes
WSF01	All	Ensuite	750	1200	-	Lead Flashing	Yes - Ref to construction notes	OQ
WSF02	All	Bedroom 1	1248	1200	-	Lead Flashing	Yes - Ref to construction notes	-
WSF03	All	Bedroom 2	1248	1200	-	Lead Flashing	Yes - Ref to construction notes	E/W
WSF04	All	Bedroom 3	750	1200	-	Lead Flashing	Yes - Ref to construction notes	E/W

Legend: (EW - Egress Window - See Note.) (OG - Obscure Glazing.) (SG - Safety Glass.) (ST - Stepped Threshold)

***NOTE - for standard electrical TTFC cut out details refer to drawing TTFC-SD-15-A to 26.1**

Electrical Legend (Private):

- Light switch.
- 2 way light switch.
- Light switch with neon light indicator, used for towel rails.
- Downlight, IP44 Rated to Bathrooms and En-Suites.
- Pendant light fitting.
- Double switched socket @ low level.
- Heat Detector.
- Mains powered smoke detector with battery back up.
- Indicative route of electrical cable.
- Double switched socket positioned above worktop level.
- Condensing Boiler. Spec to be in accordance with SAP calculations
- Gas point to Boiler and Hob
- Battery Powered Carbon Monoxide detector unable to be silenced when CO is detected. Alarm must sound different to all others to allow occupants to distinguish between them.
- Coaxial and Sky point.
- Coaxial and CAT5.
- Switched Fused spur.
- Unswitched socket outlet operated from switched fused spur above work top level. All fused spurs to be engraved for specific use in kitchens.
- Fused connection Unit switch connected to high or low level Flex Outlet Plate.
- Double switched socket with USB points (D1500USBNR) @ worktop level in kitchens & low level in all other rooms
- External wall mounted PIR.
- Consumer Control Unit.
- Isolator for extract fan - High Level.
- Ceiling mounted continuous running extract fan
- Telecom Point
- Thermostat
- External Wall Mounted PIR.
- Grid switch engraved with relevant appliance.
- Shaver Socket.
- External double switched socket.

Miscellaneous Legend (Flats):

- SVP — Denotes location of Svp.
- RWP — Denotes position of rainwater pipe.
- FG — Indicates location of Floor Gulley.
- Floor spans shown indicative only. Ref to Structural Engineer's and specialist designer's layouts for details.
- Denotes Location of cavity fire sock.
- MJ — Movement Joint Location taken from information provided by the Engineer.
- Ceiling mounted Continuous running extract fan, extracting at rate 08l/s.
- Continuous running extract/ cooker hood fan over hob, extracting at 13l/s. Fitted with chimney hood and ducted to atmosphere.
- IE — Condensing Boiler. Spec to be in accordance with SAP calculations.
- GAS — Position of ground mounted Gas meter (GSEPL approved).
- WGF01 — Denotes external window/ door reference. Refer to relevant external window & door schedules for info.
- GD01 — Denotes internal communal door reference. Refer to relevant internal door schedules for information.
- Location of FD30 self closing fire door
- Defines 30 minute fire rated enclosure to protected hallways, including ceilings

No.	Date	Amendment	Initials
P5	13.11.19	Ventilation and rain water drainage updated as client MRG comments.	
P4	08.09.19	Drawing prepared for B. Control	CC
P3	03.09.19	Plot handings revised	CC
P2	07.08.19	Retaining structure revised	CC
P1	25.07.19	Preliminary Issue	CC

Client : James Barnes

Project : Land Adjacent 85 Colchester Road, Maldon

Drawing : Ground floor Plan

Scale : 1:50 @ A1

Date : June 2019

Status : Preliminary


Rev. P5

Dwg No : 19-2943-02


GRAFIK

Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0DZ
T +44 (0)1277 658 233
F +44 (0)1277 656 234
www.grafik.uk.com

© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.



Section A-A



Section B-B

No.	Date	Amendment	Initials
P5	09.11.19	Party wall alignment amended and sacrificial walls removed	LC
P4	08.09.19	Drawings prepared for B. Control	CC
P3	04.09.19	Section B-B added	CC
P2	07.08.19	Retaining structure revised	CC
P1	25.07.19	Preliminary issue	CC

Client : James Barnes

Project : Land Adjacent 85 Colchester Road, Maldon

Drawing : Section A-A & B-B

Scale : 1:50 @ A1

Date : June 2019

Status : Preliminary


Dwg No : 19-2983-08

Rev P5

GRAFIK

Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0GZ
T +44 (0)1277 658 253
F +44 (0)1277 656 224
www.grafikuk.com


© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.



South-west Elevation

Plots 9-32


Scale 1:100




East Elevation

Plots 9-32

Scale 1:100






South-east Elevation

Plots 9-32


Scale 1:100



North-east Elevation

Plots 9-32

Scale 1:100



North-west Elevation

Plots 9-32

Scale 1:100

General Legend (Elevations):

- Indicates areas of facing brickwork. Refer to materials schedule for details of colours etc.
- Indicates areas of contrasting facing brickwork. Refer to materials schedule for details of colours etc.
- 81- W010 — Indicates window references. For external door and window schedule, refer to General Arrangement dwgs.
- GAS — Denotes location of ground mounted gas meter (SSEPL approved).
- * — Indicates location of Safety Glass. Please refer to the external door & window schedules for confirmation of specifcation etc.
- B.F — Indicates position of boiler flue
- CH.E / B.E — Indicates position of extract ventilation terminals. At to be in accordance with Specialist ventilation design. :- Cooker Hood Extraction Bathroom Extraction

Materials Legend (Elevations):

- Facing brick - Refer to materials schedule
- Feature brick - Grey Refer to materials schedule
- Black, Rainwater Goods
- White U-PVC, Windows.
- Proprietary Canopy
- Gas Riser
- Proprietary Juliet Balcony
- Opaque panels
- Roof Tiles - Refer to materials schedule
- White, Fascias / Soffits

Note: Client to provide specifications for all of the above.

General Notes (Elevations):

1. For typical window jamb & cill detail references, refer to GA plans and sections.
2. For confirmation of all proposed external finished ground levels refer to Civil Engineer's drawings.
3. Temporary works designers must ensure that the temporary works design has been approved by the Structural Engineer.
4. All movement joints to be in accordance with Structural Engineers details and specification.
5. DPC and rainwater pipes are shown indicative only. Please refer to external works plan and relevant Civil Engineers's drawings for confirmation of such items.

For Block 3.

For Substructure Plans, Refer to Dwg Nos. 19-2861-100-028 to 029.
For Substructure Construction Details, Refer to Dwg Nos. 19-2861-001 to 009.
For Block 3 GA Plans, Refer to Dwg Nos. 19-2861-230-01 to 07.
For Block 3 GA Roof Plan, Refer to Dwg Nos. 19-2861-230-08 to 09.
For Block 3 GA Elevations, Refer to Dwg No. 19-2861-230-10.
For section A-A, please refer to Dwg number: 19-2861-230-11.
For section B-B, please refer to Dwg number: 19-2861-230-12.
For section C-C & D-D, please refer to Dwg number: 19-2861-230-13.
For Superstructure Consruction Details, Refer to Dwg Nos. 19-2861-30-01 to 06.
For Construction Spec, Refer to Document Ref. Bellway Standards Consruction Specification.
For External Works Plans, Refer to Dwg Nos. 19-2861-90.

No.	Date	Amendment	Initials	No.	Date	Amendment	Initials
T2	10.10.19	Bike shelter increased and lobby introduced.	AK				
T1	30.08.19	Super Structure - CH01 ISSUE	NBF				

Client : Bellway Homes Ltd. (South London).

Project : Scotts Farm, Ewell

Drawing : Flat Block 3 - Elevations

Scale : 1:100 @ A1 | Status : Tender | Rev : T2

Date : August 2019 | Dwg No : 19/2861-230-10

GRAFIK
Grafik Architecture
Station Court
Radford Way
Billericay,
Essex CM12 0GZ.
T +44 (0)1277 658 233
F +44 (0)1277 658 234
www.grafikuk.com

©THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.


04

Buckthorn Grange
Ewell, Surrey

Bellway Homes

2019

161 unit site including 3 No. bespoke flat blocks and high end residential dwellings.



No.	Date	Amendment	Initials
T2	10.10.19	Bike shelter increased and lobby introduced	AK
T1	30.08.19	Super Structure - CH01 ISSUE	NBF

Client : Bellway Homes Ltd. (South London).

Project : Scotts Farm, Ewell

Drawing : Flat Block 3 - Ground Floor Plan Sheet 1

Scale : 1:50 @ A1

Date : August 2019

Status : Tender


Rev. T2

Dwg No : 19-2861-230-01


GRAFIK

Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0DZ
T +44 (0)1277 658 233
F +44 (0)1277 468 284
www.grafik.com


© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.



Section C-C
Scale 1:50



Section D-D
Scale 1:50



External Wall Legend (Brickwork):

303mm Cavity wall construction (u-value 0.26W/m²K) comprising:
- 103mm approved facing brick outer skin laid in stretcher bond except where elevations show otherwise) with bucket handle joints (mortar mix and brickwork to NHBC Standards Chapter 6, substrate rendering where required by Structural Engineer). Facing brickwork to extend 3 courses below finished ground level. For details of external finishes, see materials schedule and specification.
- 100mm cavity fully-filled with Knauf Supafil 36 (thermal conductivity 0.034W/mK), or similar approved, injected glass mineral wool insulation. Overall wall build-up achieves u-value of 0.25W/m²K).
- 100mm thick lightweight block inner leaf (thermal conductivity 0.15W/mK), or similar approved. Density to be between 450kg/m³ and 600kg/m³. Strengths to be as indicated upon the GA plans and as specified by the Structural Engineer.
- Internal wall finish is to be 1no. layer British Gypsum wallboard (nominal 9kg/m² mass per unit area), or similar approved, on plaster dabs.
- Provide 225mm long type kih stainless steel wall ties, by Ancon or similar approved, setat 450mm vertical and 900mm horizontal staggered centres. Specification to be confirmed by the Structural Engineer.
- 2PC to be 2000 gauge polythene in accordance with BS743 and located minimum 150mm above external ground level. Refer to detailed construction drawings.
- Cavity wall insulation to fill the full extents of the cavity, height, width and depth in accordance with the MWA insulation guidance.
- All fittings to the external leaf (for example canopies and railings) are to be fixed in accordance with Structural Engineer's instructions.
- Generally, close cavity at door and window openings with a proprietary insulated cavity closer (with conductivity 0.038 W·m·¹·K·¹ or less). All windows and doors are to be positioned within opening in such a way to avoid cold bridging, generally, front of frame to overlap the outer leaf by 39mm. Openings in external walls generally to have cavity trays over with minimum 2no. weep holes at 450mm maximum centers.
- All window jambsare to be constructed in accordance with Bellway Constructive Standard Detail.
- Generally, continuous cavity fire stops are to be provided at all separating wall and floor junctions in the form of an oversized sleeved mineral wool cavity sock, by Rockwool or similar.
- Wall ties are to be provided at maximum 225mm centres around all window and door openings and no more than 225mm from either side of all masonry expansion joints.
- Where an external wall extends into a garage, the section of outer leaf which falls within the cross sectional area of the same can be constructed in brickwork.
- Please refer to the working drawing elevations for confirmation of any bed joint reinforcement requirements, read in conjunction with the Structural Engineer's specification.

700* = Asterix indicates non-brickwork dimensions

Party Wall Legend :

300mm masonry party wall (u-value 0.00W/m²K) construction comprising:
- 2 No. leaves 100mm thick concrete blockwork. Density to be between 1350kg/m³ and 1600kg/m³. Strengths to be as specified by the Structural Engineer.
- 100mm thick Supafil Party Wall Wool, or similar approved within cavity (no gaps to remain), strictly in accordance with Robust Detail E-WM-30.
- Provide 225mm long Ancon HRT4, or similar approved, wall ties as described in BS EN 845-11:2003 and 30140 and spaced at 450mm vertical and 900mm horizontal centres (not staggered) to all party walls.
- Walls to be finished with 1no. layer 12.5mm British Gypsum Wallboard Ten (nominal 9kg/m² gypsum based), or similar approved. Plasterboard to be on plaster dabs and applied to both sides. Mortar joints to cover the full thickness of the blocks, leave no voids.
- Cavities between external and separating walls to be linked and cavity insulation carried across separating walls to form continuous cavity barrier. Alternatively, where manufacturer's technical literature permits, continue the full fill cavity wall insulation to act as fire stop.
- Party wall construction is to continue up to the underside of the roof finish and junction between separating wall and roof filled with a flexible mineral wool fire stop closer.
- All chases for services are to be kept to a minimum and filled well with mortar. Stagger chases on each side of the wall to avoid them being back to back.
- Cabnic, or similar approved, coil mesh 64mm bed joint reinforcement is to be placed within each leaf at 450m vertical centres for the full height of the party wall, unless otherwise advised by the Structural Engineer.
- Party wall construction is to be strictly in accordance with Robust Detail E-WM-30.
- Make sure that there is no connection between the two leaves of masonry except for the wall ties, insulation and foundations.
- Due consideration should be given to the requirements associated with Bellway Constructive Detail Numbr CD0027 in respect of thermal bridging at party wall junctions. It should be noted that the party wall construction, noted previously within this document, is to be adhered to for Robust Detail Compliance.

Internal Partition Legend:

70mm metal stud partition comprising:
- British Gypsum Gyproc Classic metal stud partition, or similar approved. To be finished with 1no. layer 12.5mm British Gypsum SoundBloc, or similar approved, applied to both sides.
- Denotes Metal stud buttress wall location, as advised by the Struct' Engineer. To be lined with 9mm OSB screwed to each side of the wall for the full height of the wall, & for the horizontal extent indicated on the floor plans. Please refer to Drawing No. 19-2861-50-10 Detail 21A. Applies to walls adjoining external walls only.

General Note: All metal studwork to be continued through the suspended ceiling and fixed to the underside of the structural slab utilising a suitable deflection detail, fire rated to walls forming the protected hallway, in accordance with British Gypsum standard details. Where ply lining is required, as shown on the dry lining diagram, this is to be incorporated within the depth of the stud using British Gypsum service plate fixings.

CB - Denotes contrasting brick

General Note:
All block strengths and locations indicated on this drawing have been taken from marked-up information provided by the Structural Engineer.
Important Note:
All block strengths are for superstructure masonry only.


For Block 3.
For Substructure Plans, Refer to Dwg Nos. 19-2861-100-028 to 029.
For Substructure Construction Details, Refer to Dwg Nos. 19-2861-001 to 009.
For Block 3 GA Plans, Refer to Dwg Nos. 19-2861-230-01 to 07.
For Block 3 GA Roof Plan, Refer to DwgNos. 19-2861-230-08 to 09.
For Block 3 GA Elevations, Refer to Dwg No. 19-2861-230-10.
For section A-A, please refer to Dwg number: 19-2861-230-11.
For section B-B, please refer to Dwg number: 19-2861-230-12.
For section C-C & D-D, please refer to Dwg number: 19-2861-230-13.
For Superstructure Construction Details, Refer to Dwg Nos. 19-2861-30-01 to 05.
For Construction Spec. Refer to Document Ref Bellway Standards Construction Specification.
For Externa Works Plans, Refer to Dwg Nos. 19-2861-90.

No.	Date	Amendment	Initials	No.	Date	Amendment	Initials
T2	10.10.19	Bike shelter increased and lobby introduced	AK				
T1	30.08.19	Super Structure - CH01 ISSUE	NRF				


Client : Bellway Homes Ltd. (South London).
Project : Scotts Farm, Ewell
Drawing : Flat Block 3 - Section C-C & D-D
Scale : 1:50 @ A1
Date : August 2019
Status : Tender
Rev: T2
Dwg No : 19-2861-236-13

GRAFIK
Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0DZ
T +44 (0)1277 658 233
F +44 (0)1277 658 234
www.grafik.uk.com


© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.




21A. Typical Buttress Wall / External Wall Junction Detail.
Scale 1:10




21B. Typical Internal Metal Stud Partition & External Wall Junction Detail (Plan)
Scale 1:10




22. Typical Internal Door Jamb Detail (Plan)
Scale 1:10




23. Typical Internal Door Head Detail
Scale 1:10



24. Typical Flat Entrance Door Jamb Detail
Scale 1:10




25. Typical Upper Floor Flat Entrance Threshold Detail (Flats)
Scale 1:10




26. Typical Staircase Balustrade Fixing Elevation Detail
Scale 1:10


Note: Final design to fabricators details. Structural Engineer to advise on final fixing detail to PC stairs.




27. Typical Staircase Balustrade Fixing Section Detail
Scale 1:10



28. Typical Communal Staircase Section & Balustrade Fixing Secton Detail
Scale 1:10



29.Balcony Detail Section (TBC)
Scale 1:10



30. Juliet Balcony Detail (TBC)
Scale 1:10

For Block 1.
For Substructure Plans, Refer to Dwg Nos. 19-2861-100-026.
For Substructure Construction Details, Refer to Dwg Nos. 19-2861-001 to 009.
GA Plans, Refer to Dwg Nos. 19-2861-200-01 to 04.
For Block 1 GA Roof Plan, Refer to Dwg Nos. 19-2861-200-05
For Block 1 GA Elevations, Refer to Dwg No. 19-2861-200-06.
For section A-A, please refer to dwg number: 19-2861-200-07.
For section B-B, please refer to dwg number: 19-2861-200-08.
For Superstructure Construction Details, Refer to Dwg Nos. 19-2861-30-01 to 66.
For Construction Spec, Refer to Document Ref Bellway Standards Construction Specification.
For External Works Plans, Refer to Dwg Nos. 19-2861-90

For Block 2.
For Substructure Plans, Refer to Dwg Nos. 19-2861-100-027.
For Substructure Construction Details, Refer to Dwg Nos. 19-2861-001 to 009.
GA Plans, Refer to Dwg Nos. 19-2861-200-01 to 04.
For Block 1 GA Roof Plan, Refer to Dwg Nos. 19-2861-200-05
For Block 1 GA Elevations, Refer to Dwg No. 19-2861-200-06.
For section A-A, please refer to dwg number: 19-2861-200-07.
For section B-B, please refer to dwg number: 19-2861-200-08.
For Superstructure Construction Details, Refer to Dwg Nos. 19-2861-30-01 to 66.
For Construction Spec, Refer to Document Ref Bellway Standards Construction Specification.
For External Works Plans, Refer to Dwg Nos. 19-2861-90

For Block 3.
For Substructure Plans, Refer to Dwg Nos. 19-2861-100-028 to 029.
For Substructure Construction Details, Refer to Dwg Nos. 19-2861-001 to 009.
For Block 3 GA Plans, Refer to Dwg Nos. 19-2861-200-01 to 07.
For Block 3 GA Roof Plan, Refer to Dwg Nos. 19-2861-200-08 to 09.
For Block 3 GA Elevations, Refer to Dwg No. 19-2861-200-10.
For section A-A, please refer to dwg number: 19-2861-200-11.
For section B-B, please refer to dwg number: 19-2861-200-12.
For section C-C & D-D, please refer to dwg number: 19-2861-200-13
For Superstructure Construction Details, Refer to Dwg Nos. 19-2861-30-01 to 66.
For Construction Spec, Refer to Document Ref Bellway Standards Construction Specification.
For External Works Plans, Refer to Dwg Nos. 19-2861-90.

Note: Refer to External Material Schedule for confirmation of external materials, Brick Types, Colours and Locations.

General Notes:
Temporary works designers must ensure that the temporary works design has been approved by the Structural Engineer.

Due consideration should be given to the requirements associated with The Constructive Details, in respect of thermal bridging.

All plasterboard finishes within wet areas are to be suitably moisture resistant. Please refer to the British Gypsum specification for further details.

Please refer to Structural Engineer's drawings for full details of all reinforced concrete structure.

For confirmation of all blockwork types, please refer to GA plans.

No.	Date	Amendment	Initials
T2	26.11.19	Revised in line with client comment	CC
T1	30.08.19	Superstructure CH01 Issue	KS

Client : Bellway Homes Ltd. (South London).

Project : Scotts Farm, Ewell

Drawing : Typical Superstructre Details Sheet 5

Scale : 1:10@ A1

Date : August 2019

Status : Tender

Dwg No : 19-2861-30-05

Rev T2

GRAFIK

Grafik Architecture
Station Court
Radford Way
Billericay
Essex CM12 0GZ
T +44 (0)1277 658 233
F +44 (0)1277 656 234
info@grafikuk.com

© THIS DRAWING IS THE COPYRIGHT OF GRAFIK ARCHITECTURE. It shall not be in any way used or reproduced without their prior written consent. All dimensions are to be checked on site or in the workshop prior to commencing any work. Work only to figured dimensions. Any discrepancies are to be reported to the Architect.

M:\Projects\19\2861 Scotts Farm Road, Ewell\Working\BETA\LB AND EXTERNAL\Drawings\dwg - Superstructure Details

Skills

- AutoCAD & SketchUp proficient
- Management of staff, consultants & contractors
- Management of Planning/Building Regulations and NHBC conditions approval
- Frequent attendee at networking events across the UK
- Full, clean UK driving license
- CSCS card



Caius Colfer

Preston, Lancashire

Contact Information

Linked In: Caius Colfer

07961556279

caiuscolfer@yahoo.co.uk

References available upon request